IV-02-Meigo



Proton Beam Window Assembly (PBW Assy)

S. Meigo and T. Teraoku(JAERI)

meigo@linac.tokai.jaeri.go.jp



Outline

- Design of PBW
 - Philosophy
- Analysis for thermal hydraulic and stress
 - Temperature and stress
- Shielding plug
- Beam monitor and other equipments
- Maintenance scenarios







Cause blow up of primary beam, which is injected to reflector. Blow up diminish as increase of energy.

Concept of PBW









Intensity Proton Accelerator Project

Obsolete design used parallel plates window









Evaluation of stress due to internal pressure





- 0.5 mm thickness for IN718 is satisfied for the stress.
- However, 1.5mm of the thickness seems to be the thinnest as for manufacturing with IN718.



Distribution of heat deposition



- Up to now, real distribution of proton beam can not be estimated. Assumptions are made.
- Heat deposition is given by Decay-TURTLE and NMTC/JAM.



Results of temperature and thermal stress for uniform dist. in phase space





For uniform case, temp. and stress are acceptable for IN-718.

Results of temperature and thermal stress for Gaussian dist. in phase space





Analysis flow distribution of H_2O



Elements: 740k mesh T H_2O H_2O PROITAR 3.10 00-100-01 100 w - 1000 - 8-248 0.217 AHOLE -95.533 P.127ABCE 0.995 1 EH (EN 1.000 1.000 1.000 1.120 EHIDE EN PLOT 450 490 120 Unit(mm)

Velocity at inlet :1 m/sec (4.8 m³/hr)



Result of wall temperature by thermal hydraulics analysis





Temperature of wall is acceptable.







Distribution of temperature for assembly

1 .Modeling (3D solid) (See the right fig.) (1)PBW

Window, Plenum and Pillow seal

(2)Plug

Flange, Shield, Supporter, Base and Guide

2 .Placement

d. Plug

Fixed by the pin located plenum Upper flange and base

- 3 .Analysis condition
- (1)Density of heat deposition
- a. Window and Plenum
- b. Duct at upstream
- c. Duct at downstream
- ••• 0.06 ~ 0.14W/cc ••• 0.0001 ~ 0.01W/cc

··· 0.3 W/cc (const)

•••0.02~0.06W/cc

••• 0.002 ~ 0.01W/cc

- e. Mount, Rough guide
- (2)Heat transfer coefficient
- a. Heat transfer for water cooling (for 40) Window 9 kW/m²K, Plenum 1 kW/m²K
- b. Air ambient (natural convection heat transfer) On surface of Duct, Plug and Base
 - 5 W/m²K, Temp. 40
- c. Vacuum region Heat transfer insulated on vacuumed area and He area







Beam Monitor





Mineral insulator cables made of MgO_2 will be used.

Heat deposition on beam monitor





Temp. will be raised up to 200 . However, power of beam will significantly smaller than 1 MW in 1st phase. We need redundant system for case of low power.

Pillow seal







Already pillow seal has been used in KEK, PSI. Although some modification will be necessary, it is feasible.

Maintenance scenarios



Life time: PBW is given 5 DPA/y. It will be used longer than 1 year. Is it enough by the estimation of DPA? (Nobody knows) How should we determine life time before plugged out? PIE is reliable. Make sure by the inspection, which is possible by fiber scope fed through multi-purpose hole.

Fiber scope



Trigger for Fast Closing Valve (FCV), which is placed in case of rupture of window, will be ahead of multi-purpose hole.

Maintenance scenarios(Cond.)



Scenario of PBW replacement :

1) During long shutdown, waiting for radiation cooling of radiation. (2 ~ 3days)

2) Surrounded by cask, old Assy is removed with remote handing tech. Transferred to cooling area (Basement floor of MLF). Used plug can be employed again after several years(>10 y).

3) Replaced new Assy by remote handing.

In case of replacement, position of new Assy is determined by Insert new Assy Hole for PBW Assy gives rough position (<20 mm). Led by rough guide (~5 mm) Course position determined by guide pin (~1 mm)

Summary



A Proton Beam Window (PBW) with curved surface is designed.

Window: IN-718 (1.5mm-t) x2, Water: 1 MPa

Analyses were performed

- 1) Stress by internal pressure due to water
- 2) Thermal stress and temperature
- 3) Earthquake resistance for plug

It is found that the present PBW is feasible.

PBW is assembled with

1) Pillow seal

2) Beam monitor

3) Hole for inspection

PBW Assy : Height 5m, Weight 10 t

Procurement of Mark-I will start this December.

For the confirmation of design, other devices such as T/C on the duct should be equipped. These data will help design for next generation of PBW Assy.